

NATIONAL JUTE BOARD

3A & 3B Park Plaza, 71, Parkstreet, Kolkata-700016

Ministry of Textiles

Govt. of India

TENDER DOCUMENT

For Renovation work at Sonali Showroom Dakshinapan CIT Complex,
2No. Gariahat Road, South, Kolkata-700068.

All rates of Schedule as per PWD/CPWD basis. 2014-15

Sl.No.	Item of work description	Qnty.	Rate	Amount
1)	Mezzanine floor fully repair new Iron, angel 75mm x 75mm ISI Slandered and Top Salwooden plank 25mm thick for platform & finaly 12mm Ply (ISI) with P.V.C.(2mm thick) Fixing Wonder/Krishna Brand also stock purpose 18mm thick Ply (ISI) Rack all Complete charge.	680Sft.		
2)	54nos window (Stell) remove and open area bricks works and plaster (1:4) C.M Sand & Cement. 30' hight working area from ground floor	650Sft.		
3)	Flooring - Wonder/Krishna variety Supply & fixing P.V.C. Flooring also 12mm ply fixing mazzanen & Staircase step also existing remove Ply & PVC flooring.	842Sft.		
4)	False ceiling - Sen Gobind / Gypsemline variety Providing fixing G.I Frame & 12mm Gypsum board fixing with painting finished.	652Sft.		
5)	Godown - Godrej / Estillo variety Godown cum display chamber one secretariate table sample Rack as per our design.	652Sft.		
6)	Manager Chamber - Godrej / Estillo variety Manager chamber covered ply and one way 10mm glass with door, one Secretariate table, with glass top and file rack etc. as per design	80Sft.		
7)	Stair case - Stair case as per design mode by Iron angel wooden step and steel handle with Railing complete.	52Sft.		

Sl.No.	Item of work description	Qty.	Rate	Amount
	<u>Ground Floor</u>			
1)	False ceiling - Sen Gobind / Gypsemline variety Providing fixing of G.I. Frame with Gusum board fixing with 2 layers as our design finished with paint Berger / Asian etc.	1460Sft.		
2)	Flooring - Flooring 2'x2'vitrified (Kajaria) Tile fixing with proper remove old area of the floor cement, for new flooring purpose finally fixing cement chemical. Also remove garbage.	1200Sft.		
3)	Glass - Modi / San Gobind variety Back & right side window (Display) with aluminum framing with 10mm terfen (tempered) glass fixing.	446Sft.		
4)	Main glass door (entrance) & show window- Front Entrance door made by 12 mm Terfen glass and floor spring 2 Nos handle and 2 Nos show window 10mm terfen glass and aluminum frame as per our design.	125Sft.		
5)	Rolling shutter- Rolling shutter taking out side from inside with repair & painting all completed.	2 No.		
6)	A.C.P. Work- Aludecor / Times variety Front Facia A.C.P. Work G.I. Frame with fixing A.C.P. Board & one sign board also.	210Sft.		
7)	A.C.P. Board works- Aludecor / Times variety Back side & right window top and buttom wall covered by G.I. Frame work and finally 3.5mm A.C.P. Board fixing.	800Sft.		
8)	Sign board as per our design Back & Front side glow sign board.	2 No.		
9)	Furniture- ISI Make Ply and Laminate Furniture Rack (display) and Delivery/ customer display counter as per our design (moveable). Rack - 8' x 7' x 16" x 13 nos Counter - 7' x 3' x 24" x 13 nos	840Sft. 315Sft.		
10)	Cash Counter- Godrej / Estillo variety Cash Counter as per our design covered by glass, ply & File rack etc.	28Sft.		

Sl.No.	Item of work description	Qty.	Rate	Amount
	Ground Floor			
11)	Round Display Rack as our design made by 12mm Ply ISI standard	2 No.		
12)	Cash Counter chair. Estillo/ Stelco make as per our design.	2 No.		
13)	Customer tolls. Stelco / Estillo make as per our design.	10No.		
14)	One aluminum ladder. MAT-X make 7'height	1No.		
15)	A.C.(1.5) ton supply & fixing 2 Nos split one (1) window. With installation Charge, Voltas / LG make.	3No.		
16)	1 No LED TV. SAMSUNG / LG make.	1No.		
17)	Cabin fan. Cormpton / Polar make.	10No.		
18)	Electrical Work-			
	A) Light point fan point fully wiring Finolex/ Havells make wire swithes etc.	125 Nos.		
	B) Plug points (computer also). Finolex/Havells	12 Nos.		
	C) Plug for light fan etc. Havells / Anchor make.	6 Nos.		
	D) CFL fitting with lamp. Phillips / Diomond make.	80 Nos.		
	E) LED 6-10 WT fitting with lamp. Diomond	18 Nos.		
	F) Main line (10mm) wire Finolex / Havells make.	25m		
	G) A.C. Line (4mm) wire Finolex / Havells make.	80m		
	H) Circuit line Finolex / Havells make.	200m		
	I) D.B. (M.C.B) for light line. Havells / HPL make.	12way		
	J) D.B. (M.C.B) for A.C. Line. Havells / Anchor	6way		
	K) 63 Amp DP Main (R.C.C.B) Havells make.	1no.		
	L) Generator line. Finolex / Havells make 6mm wire.	40m		
	M) 32 Amp change over Flowera / Havells make. above total electrical Materials & Labour	1no.		

Sl.No.	Item of work description	Qty.	Rate	Amount
19)	CCTV System - as per ISI Standard Emporium under the surveillance of close circuit camera with monitor.		L.S	
20)	Sound & Music - Philips / Clarion make Sound system with instrumental music.		L.S	
21)	POS system. TVS / HP make Computer, printer, scanner, modem & bar code reader with installation in all respect.		L.S	
22)	Painting - Berger / ICI / Asian make Showroom Painting wall, ceiling etc.	3500sft.		
23)	Solar System - ISI Slandered Power will be saved by solar system light front entrance showcase etc.		L.S	
24)	Civil Work Tacking out worm out of existing damaged roof area and properly cleaning the total top area and properly reconstruction the same area I.P.S (1:2:4) C.C. with apply Sika chemical flooring top finish with net cement to maintain 50mm thick proper slope upto rain water pipe.	1800sft.		
25)	Stripping off worm out the outside damaged plaster area and cleaning the same surface and re-plaster 25mm thick 1:4 C.M. With apply Sika chemical.	1500sft.		
26)	Mislenious.	L.S	L.S	
	Total Cost of the work			
	Say Rs.			

Rupees-

Note:-

- 1) Rate quoted including all taxes etc. Where applicable.
- 2) All details drawing enclosed by the tender as per tender schedule which is first preference to the authority to select the contractors.
- 3) Enclosed with floor drawing with tender documents.